No.	Items of work	Per.	Quantity
	Sluice cill R. L. 44·00.		
1	Cut opening the bund and refilling with watering and tamping.	C.yd.	62
2	Putting stone Jelly concrete in surki mortar ...	C.ft.	262
3	Burnt brick in surki mortar	C.ft.	280
4	Supplying new burnt stone slabs 6" thick dressed and fixed.	S.ft.	64
5	Cutting holes for orifice	Each	3
6	Pointing with cement to exposed portions	Sqr.	2
7	Supplying new cast iron pipe 4" dia and fixing with cement and hump joint.	R.ft.	31½
8	Suppling Jally wood plug with iron rod and fixing with locking arrangements.	L. S.	...
	Weir R. L. 50·00.		
1	Earthwork excavating foundation in hard soil and using the same for the wing.	C.yds.	64
2	Stone jelly concrete in surki mortar	C.ft.	285
3	Burnt brick in surki mortar	,,	749
4	Supplying new burnt stone slabs with jojjle joints and dressing for coping including fixing in surki mortar.	S.ft.	134
5	Plastering with surki mortar	Sqr.	9·22
6	Constructing apron and wing wall with available stones and jelly packing.	C.yd.	27–

Abstract Notification, dated 12th May 1933.

"The attention of the public is invited to the detailed notification calling for tenders for 'Restoring Achammanahalli Tank, in Krishnarajpete Taluk, published in pages 561 and 562, Part VI of the *Mysore Gazette*, dated 18th May 1933.

Last date for receiving tenders is 5th June 1933 till 12 noon.

Abstract Notification, dated 28th April 1933.

The attention of the public is invited to the detailed notification calling for tenders for Restoring Bendarvadi minor tank reg. No. 6 of Malvalli Taluk, published in pages 506 and and 507, Part VI of the *Mysore Gazette*, dated 11th May 1933.

The last date for the receipt of tenders is extended from 22nd May to 7th June 1933.

K. NARAYANA IYENGAR,
Executive Engineer.

ARASALU-ANANDAPURAM RAILWAY CONSTRUCTION DIVISION.

Notification dated 23rd May 1933.

Sealed tenders are invited from contractors who are willing to undertake Construction of Indian Refreshment Room at Anandapuram on Arasalu-Anandapuram Railway.

2. Tenders should be submitted in special form which can be obtained from the Assistant Engineer-in-charge, Arasalu-Anandapuram Railway Construction Division, Shimoga, on payment of Rs. 2 which amount is not refundable under any circumstances.

3. Tenders should be addressed to the Assistant Engineer-in-charge, Arasalu-Anandapuram Railway Construction Division, Shimoga, and should reach him not later than 4 P.M., on 15th June 1933 in sealed covers superscribed "Tender for Indian Refreshment Room at Anandapuram."

4. No tender will be considered which is not in the prescribed form.

5. Rates should be noted both in figures and in words. Tenders which quote rates as "Estimate Rates" or some per cent more or less will not be considered.

6. The work tendered should be completed in all respects by 31st December 1933.

7. The name of the accepted tenderer will be posted on the notice board of the Assistant Engineer's Office, Shimoga, soon after the approval by the Superintendent, Way and Works, Mysore Railways, Mysore, and no enquiries regarding the acceptance or rejection of tenders will be replied.

8. The final acceptance of the tender will rest with the Superintendent, Way and Works, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself, the right to reject without assigning any reason therefor, any or all the tenders or any portion of any one tender.

9. Every tender should be accompanied by an earnest money of Rs. 100 which can be

10. The earnest money of the successful tenderer will be accepted as part payment towards deposit due by him as per para 14 below.

11. The earnest money of unsuccessful tenderers will be returned as soon as the tenders are disposed of.

12. Tenders which are not accompanied with the earnest money specified in para 9 *supra* will not be considered.

13. Successful tenderers should execute within eight days from the date of acceptance of tenders, the usual Railway Schedule Contract Bond. Failure to comply with this condition, will render the tenderer liable for forfeiture of earnest money.

14. Successful tenderers should deposit with the Assistant Engineer-in-charge, Shimoga, before they sign the schedule agreement, 5 per cent of the value of work given out to them, such sum not to exceed to Rs. 180.

15. Work should be started within 15 days from the date of acceptance of tenders and the stipulated monthly progress should be kept up, failing which, the contractor shall pay a penalty as may be fixed by the Superintendent, Way and Works, for delay unaccounted for or not satisfactorily explained in completing the work as per terms of agreement and in addition, shall forfeit his deposit.

16. Sub-letting of work or transferring Powers under Power of Attorney to others is strictly prohibited.

17. Plans specifications and other details of work to be done are available for inspection in the Assistant Engineer's Office, Shimoga, where intending contractors may call and obtain necessary information during office hours.

18. In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintendent, Way and Works, will be final and legally binding.

Schedule of approximate quantities of work to be done for constructing Indian Refreshment Room at Anandapuram.

Sl. No.	Particulars	Unit	Quantity	Remarks
1	Earth work excavation in laterite soil and filling in ..	C.ft. 1000	1,000	
2	Laterite in clay	„ 100	4,100	
3	Laterite in lime mortar—arch work	„	75	
4	Laterite in lime mortar—coping	R.ft.	55	
5	Teakwood doors with battened shutters providing 9" tower bolts at top, middle and bottom, hasps and staples, hooks eyes clamps at sides, etc., complete. (scantling of door frame to be 5" x 4" for 7 ft. doors and 4" x 3" for 6½ ft. doors).	S.ft.	320	
6	Teakwood windows with battened shutters and ¾" diameter iron bars, hooks, eyes, and all fittings complete including clamps for frame to go inside wall.	„	145	
7	Teakwood rectangular ventilators with ¾" iron bars and glazed shutters including all fittings complete.	„	6	
8	Teakwood cup-boards with two rows of planks 1" thick panelled shutters and all fittings complete including clamps for frame.	„	25	
9	Supplying and fixing burnt stone slabs 6" thick one line dressed.	„	25	
10	Cement concrete slabs 6" thick including plastering in cement for cills of doors and windows (proportion for cement concrete 1: 2: 5).	C.ft. 100	30	
11	Teakwood wrought and put up including wood oiling two coats complete.	C.ft.	62	
12	Roofing with Mangalore pattern tiles on teak reepers 2" x 1" including chunam borders, wind ties, etc., complete with clamps for rafters.	S.ft. 100	2,000	
13	Ridge tiles set in mortar and cement pointed ...	R.ft.	135	
14	Fixing 41½ lbs. sec. rails	„	120	
15	Chunam plastering	S.ft. 100	5,200	
16	White washing two coats	„	5,200	
17	Cement pointing (proportion 1: 1)	„	300	
18	Cement plastering (proportion 1: 2)	„	150	
19	Flooring with stone jelly concrete in chunam 6" thick plastered over with ¼" cement, size of jelly not	„	1,100	

...t, rails, roofing and ridge tiles, etc., will be supplied departmentally free of cost at Anandapuram.